

AD-A126 550


A FIBER-OPTIC LINK FOR USE WITH MICROWAVE FIELD SENSORS  
(U) HARRY DIAMOND LABS ADELPHI MD J C BLACKBURN ET AL.  
MAR 83 HDL-TM-83-2


1/1

UNCLASSIFIED

F/G 14/2

NL





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

ADA 126550

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER HDL-TM-83-2	2. GOVT ACCESSION NO. AD-A126550	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle)  A Fiber-Optic Link for Use with Microwave Field Sensors	5. TYPE OF REPORT & PERIOD COVERED Technical Memorandum	
7. AUTHOR(s)  James C. Blackburn Peter Li	6. PERFORMING ORG. REPORT NUMBER	
9. PERFORMING ORGANIZATION NAME AND ADDRESS Harry Diamond Laboratories 2800 Powder Mill Road Adelphi, Maryland 20783	8. CONTRACT OR GRANT NUMBER(s)	
11. CONTROLLING OFFICE NAME AND ADDRESS	10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS Program Ele: 62120A DA No: 1L162120AH25	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)	12. REPORT DATE March 1983	
	13. NUMBER OF PAGES 19	
	15. SECURITY CLASS. (of this report) UNCLASSIFIED	
	15a. DECLASSIFICATION/DOWNGRADING SCHEDULE	
16. DISTRIBUTION STATEMENT (of this Report)  Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES  Project No. E01228 DRCMS Code: 612120H250011		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number)  Fiber optics Optical signal link LED		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number)  ► The paper describes two types of compact fiber-optic links designed to provide dielectric isolation and noise immunity to the interconnection of miniature microwave field-sensor probes and remotely located test equipment. The system measures the microwave signal levels leaking into partially shielded electronic packages. The fast-rise link (rise time <3 ns) is for use where the microwave irradiation source produces radar-like short pulses. The high-sensitivity link (input noise level <3 $\mu$ V) is for use with laboratory 1-kHz modulated microwave sources. The transmitters are the size of a gum eraser, 1 1/4 x 1 1/4 x 2 3/8 in. The 15-V dc power for the transmitters is obtained either from the system under test or a small NiCd battery.		

DD FORM 1473

EDITION 1 NOV 63 IS OBSOLETE

UNCLASSIFIED

1 SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

## CONTENTS

	<u>Page</u>
1. INTRODUCTION .....	5
2. FAST-RESPONSE LINK .....	5
2.1 Transmitter .....	5
2.2 Receiver-Controller .....	10
3. HIGH-SENSITIVITY LINK .....	12
4. CONCLUDING REMARKS .....	13
DISTRIBUTION .....	15

## FIGURES

1. Optical transmitter and receiver .....	6
2. Close-up view of optical transmitter .....	6
3. Photo of fast-response transmitter board .....	7
4. Schematic of fast-response transmitter .....	7
5. Photo of control/calibrator/regulator board for transmitter .....	8
6. Schematic of control/calibrator/regulator board .....	9
7. Schematic of optical receiver and control .....	10
8. Comparison of microwave detector signal as carried by coaxial cable and as carried by fast-response optical link .....	11
9. Schematic of high-sensitivity 1-kHz transmitter .....	12

DTIC  
COPY  
INSTRUMENT  
2

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/	
Availability Codes	
Avail and/or	
Special	

A

## 1. INTRODUCTION

The fiber-optic signal links described here were built as a part of a system which measures microwave leakage into electronic packages with the purpose of determining those levels which produce upset or damage. The rf levels are sensed by a subminiature rf probe and crystal detector which is described elsewhere.\* The extremely small size of this probe allows determination of the field in a highly localized area. Fiber optics was chosen as the method of connecting the probe's output to external equipment in order to avoid the undesirable effects of conducting cables. Conductors may pick up extraneous electromagnetic noise, especially in the case of small microwave levels at the detector, where the signal output may be measured in microvolts; conductors also alter the microwave fields in the vicinity where they penetrate the electronics enclosures.

## 2. FAST-RESPONSE LINK

The optical signal transmission system shown in figure 1 is intended for use with pulse-modulated microwave sources and was accordingly designed for a rise time  $< 3$  ns and to have negligible droop at tens of microseconds. The unipolar signal level from the probe ranges from about 1 mV to several tens of millivolts, setting the sensitivity requirement for the fiber-optic transmitter. A prime requirement for the transmitter was that it be of small size so that both it and the detector could be placed in confined areas. Figure 2 shows that the transmitter is the size of a gum eraser, about  $1\frac{1}{4} \times 1\frac{1}{4} \times 2\frac{3}{8}$  in. The power supply is external, in many cases supplied by the equipment under test. There were no size requirements upon the receiver except that it fit a standard rack.

Two fibers can be seen leaving the transmitter (see fig. 2, right side of case). These attach to the two optical connectors on the front panel of the receiver. One of the fibers carries the analog signal from the transmitter to receiver and the other control signals from the controller (in the receiver box) to the transmitter. Both fibers are 100- $\mu$ m-core step-index fibers which are inexpensive, readily available, and compatible with all-plastic connectors. All-plastic connectors must be used because it is not permissible to have metallic connectors near the object being tested. Fiber "extension cords" up to thousands of feet in length may be inserted as desired.

### 2.1 Transmitter

The transmitter contains two circuit boards, each  $1 \times 2\frac{1}{4}$  in., mounted one on top of the other. One board amplifies the input signal and applies it to the light-emitting diode (LED), thus producing the analog optical signal. The second board contains a calibration pulse generator, a voltage regulator, a battery condition sensor, and a command receiver.

---

\*R. V. Garver, Interim (6 month) Report for the Directed Microwave-Energy Vulnerability Program. To be published. HDL-PRL



Figure 1. Optical transmitter and receiver.




Figure 2. Close-up view of optical transmitter.

The transmitter board is shown in detail in figure 3 and its circuit in figure 4. An unusual construction is used, with the larger semiconductors fastened into shallow wells in the circuit board with their leads upward. Small components are soldered directly between these leads. The lead lengths are quite short and therefore rigid; the finished circuit is sturdy and accessible for repair or adjustment. This arrangement allowed a closer spacing of components and shorter lead lengths than seemed attainable with a more conventional printed circuit board. Silver epoxy is used to form a good ground between semiconductor cases and the ground plane of the board.



Figure 3. Photo of fast-response transmitter board. Large brass cylinder is LED, left of it is driver Q1. Amplifiers A1 and A2 are upper center.




Figure 4. Schematic of fast-response transmitter.

A1=GPD 462; A2=GPD 461; Q1=2N5109; Q2=MM4049; LED=C86008  
ALL R'S 1/8W UNLESS INDICATED; ALL UNMARKED C'S 0.33  $\mu$ F CHIP TYPE;  
ALL UNMARKED DIODES 1N4148



The transmitter circuit is based on that of a previous system;<sup>1</sup> it is straightforward and requires little comment. R1 supplies a dc bias to the LED in addition to the steady-state current through Q1. D1, R7, and R8 provide the means of injecting the calibrator signal into the transmitter. When the calibrator is off, D1 is reverse biased and has little effect on the circuit. When the calibrator is operating, the diode is forward biased and conducts.

The controller board is shown in figure 5 and its circuitry in figure 6. IC3 section 1 (IC3-1) amplifies the output of photodetector Q4. If Q4 is dark, the output of IC3-1 is low and IC3 sections 2-4 are unbiased and therefore inoperative (and drawing no current). When Q4 is illuminated, sections 2-3 are biased on by the current through R7 and begin to function. Most important, IC5, Q4, and IC3-2 supply a regulated 12 V to the transmitter, thus causing it to operate. If Q4 is steadily illuminated, this is all that happens, and the transmitter turns on. If, however, the illumination falling on Q4 is periodically interrupted, C1 and R7 maintain the bias on IC3-2-4; yet D2, R6, and C2 provide a zero to IC3-4; this causes Q3 to turn on, thus enabling the calibration generator IC2. The frequency of the square wave produced by IC2 depends on the voltage applied to its pin 2. If the battery voltage sensed by IC3-3 is below normal, its output goes high and increases the repetition rate of IC2 to about five times its normal value; this signals the low-voltage condition to the user.





Figure 5. Photo of control/calibrator/regulator board for transmitter.

---

<sup>1</sup>J. C. Blackburn and R. Martin, A Versatile Fiber-Optic Signal Link for EMP Testing and General Laboratory Application, Harry Diamond Laboratories, HDL-TM-80-5 (June 1980).



IC2=MC1658; IC3=LM346; IC4=78L05; IC5=AD589; Q3=2N3904; Q4=MFOD202E; Q5=MJE254  
UNMARKED DIODES=IN4148; UNMARKED C'S=0.33  $\mu$ F CHIP; ALL C'S=1/8W

Figure 6. Schematic of control/calibrator/regulator board.

R2-R3, R12-R13, and R16-R17 are voltage dividers that set, respectively, optical sensitivity, regulator level, and low battery warning level. Instead of using potentiometers, which are bulky and subject to unauthorized tweaking, R3, R12, and R16 are connected by tiny component lead sockets. The appropriate value is found by temporary insertion of an external potentiometer, and the closest value of 1/8-W resistor is then inserted into the board.

The standby current consumption of the transmitter is small, less than 100  $\mu$ A. The operating current is about 110 mA (at 12 V) during signal transmission, and an additional 30 mA is required while the 1.5-MHz square-wave calibrator is operating.

No power source is contained in the transmitter. Since a voltage regulator is incorporated in the circuit, the external voltage supply can range between about 13 and 25 V. In some test situations the transmitter is operated from the internal power of the system under test. Where this is not possible, the external NiCd battery supplied with the transmitter is adequate for about two hours of operation. The power input line to the transmitter is filtered and bypassed to prevent noise from entering the transmitter case and circuits.

## 2.2 Receiver-Controller

Figure 7 shows the optical receiver circuitry. Q7, D1, IC8, and associated circuitry form a constant current source which causes the voltage on the avalanche photodiode (APD) to adjust to a value which provides a fixed current. This action compensates for both temperature effects on the APD and variations in the optical signal. Q6, IC6-1, and so on, form a voltage limiter, so that even in the absence of an optical signal the APD will not be driven to breakdown (self avalanche). A silicon diode, part of the detector module and connected between ground and module pin 8, corrects the voltage limit for ambient temperature. IC6-2 drives the indicating meter in proportion to the bias voltage on the APD; a higher reading indicates a lesser optical signal.




Figure 7. Schematic of optical receiver and control.

IC7-2 and associated components form a 10-Hz oscillator whose output is differentiated, inverted by IC7-3, and applied to Q8. Q8 drives the control signal LED (LED-1) with either a steady dc current (switch in lower position) or a waveform of 90 percent on, 10 percent off, with a pulse repetition rate of 10 Hz (switch in upper position). The steady current causes the remote transmitter to turn on; the pulsed current causes both turn-on and calibrator operation.

Figure 8 compares the microwave detector signal as transmitted by both coaxial cable and the optical link. The two waveforms match to well within 1 dB when the calibration of the optical link is taken into account.




Figure 8. Comparison of microwave detector signal as carried by coaxial cable (top) and as carried by fast-response optical link (bottom). Test performed in arrangement where presence of conducting coaxial cable was noninterfering.

### 3. HIGH-SENSITIVITY LINK

It was found necessary to provide an optical link for transmission of the low-level 1-kHz signals produced by the field sensors when the irradiation source was relatively low-power laboratory signal generators (rather than a high-power radar transmitter). In order to expedite construction, one of the high-speed links was modified, keeping as much of the original circuitry as possible.

The control board (fig. 5 and 6) was unchanged except for altering the value of R12 to provide a 9-V output and the value of the timing capacitor on IC2 to produce a 1-kHz square-wave output.

The receiver (fig. 7) was modified by taking the signal output directly from pin 1 of the detector module and eliminating A3.

The transmitter required extensive changes: A1, A2, Q1, and Q2 (fig. 4) were removed, although the circuit board (fig. 3) was saved. The circuitry of figure 9 was then installed. The LM 381 was epoxied (pins up) at the location of A1, A2 in the original circuit. The 2N2905 was located in the heat sink which held Q1 in the high-speed link. Point-to-point wiring, as in figure 3, was used.




Figure 9. Schematic of high-sensitivity 1-kHz transmitter.

To reduce the noise level at the input, one of the two transistors in the differential first stage was disabled, and the signal and feedback were applied to the base and emitter, respectively, of the remaining transistor. The noise level at the receiver output corresponds to about 3  $\mu\text{V}$  at the input to the transmitter (over a bandwidth of 10 Hz to 10 kHz); gain from input to output is about 55 dB. The maximum linear input is about 350  $\mu\text{V}$ . If a tuned detector, such as a Hewlett Packard 3410 microvolt meter, is placed at the receiver, input signal levels on the order of 0.1  $\mu\text{V}$  can be measured.

#### 4. CONCLUDING REMARKS

The simple circuits in the transmitter could obviously be hybridized, resulting in an even smaller package. The present configuration did meet all needs of the experiment and was relatively quick and economical to build. A single-fiber connection scheme was considered in which the signal LED (LED 1 of fig. 4) would serve as a detector for control commands before being biased "on" for transmission. This would have the desirable result of saving one interconnecting fiber-optic cable, but would increase the size of the control circuitry somewhat; such a scheme would also require several mechanical and optical components in the fiber-to-detector path in order to switch the fiber between the function of carrying control signals from receiver to transmitter and that of carrying data from transmitter to receiver. This single-fiber approach was not implemented in this system because the difficulties associated with a second (control) fiber were minor. Where long fiber runs are needed, or access for laying cables is limited, the single fiber might have considerable advantage.

## DISTRIBUTION

ADMINISTRATOR  
DEFENSE TECHNICAL INFORMATION CENTER  
ATTN DTIC-DDA (12 COPIES)  
CAMERON STATION, BUILDING 5  
ALEXANDRIA, VA 22314

COMMANDER  
US ARMY RSCH & STD GP (EUR)  
ATTN CHIEF, PHYSICS & MATH BRANCH  
FPO NEW YORK 09510

COMMANDER  
US ARMY MISSILE & MUNITIONS  
CENTER & SCHOOL  
ATTN ATSK-CTD-F  
REDSTONE ARSENAL, AL 35809

DIRECTOR  
US ARMY MATERIEL SYSTEMS ANALYSIS  
ACTIVITY  
ATTN DRXS-MP  
ABERDEEN PROVING GROUND, MD 21005

DIRECTOR  
US ARMY BALLISTIC RESEARCH LABORATORY  
ATTN DRDAR-TSB-S (STINFO)  
ABERDEEN PROVING GROUND, MD 21005

US ARMY ELECTRONICS TECHNOLOGY  
& DEVICES LABORATORY  
ATTN DELET-DD  
FT MONMOUTH, NJ 07703

HQ, USAF/SAMI  
WASHINGTON, DC 20330

DEPARTMENT OF COMMERCE  
NATIONAL BUREAU OF STANDARDS  
ATTN LIBRARY  
ATTN CENTER FOR RADIATION RESEARCH  
WASHINGTON, DC 20230

DIRECTOR  
DEFENSE ADVANCED RESEARCH  
PROJECTS AGENCY  
ARCHITECT BLDG  
ATTN MATERIALS SCIENCES  
ATTN ADVANCED CONCEPTS DIV  
ATTN TARGET ACQUISITION  
& ENGAGEMENT DIV  
ATTN WEAPONS TECH & CONCEPTS DIV  
1400 WILSON BLVD  
ARLINGTON, VA 22209

DIRECTOR  
DEFENSE COMMUNICATIONS AGENCY  
ATTN TECH LIBRARY  
ATTN COMMAND & CONTROL TECHNICAL  
CENTER  
WASHINGTON, DC 20305

DIRECTOR  
DEFENSE COMMUNICATIONS ENGINEERING  
CENTER  
ATTN TECHNICAL LIBRARY  
1860 WIEHLE AVE  
RESTON, VA 22090

DIRECTOR  
NATIONAL SECURITY AGENCY  
ATTN TECHNICAL LIBRARY  
FT MEADE, MD 20755

DIRECTOR  
DEFENSE NUCLEAR AGENCY  
ATTN DDST, E. E. CONRAD, DEP DIR  
SCIENCE & TECHNOLOGY  
ATTN TISI, SCIENTIFIC INFORMATION DIV  
ATTN TITL, TECHNICAL LIBRARY DIV  
ATTN SPTD, TEST DIVISION  
ATTN RAAE, ATMOSPHERIC EFFECTS DIV  
ATTN RAEV, ELECTONICS  
VULNERABILITY DIV  
ATTN RAAE, EMP EFFECTS DIV  
WASHINGTON, DC 20305

COMMANDER  
FIELD COMMAND  
DEFENSE NUCLEAR AGENCY  
ATTN FCPR  
ATTN FCSD-A4, TECH REF BR  
KIRTLAND AFB, NM 87115

UNDER SECRETARY OF DEFENSE  
FOR RESEARCH & ENGINEERING  
ATTN TEST & EVALUATION  
ATTN RESEARCH & ADVANCE TECH  
WASHINGTON, DC 20301

DIRECTOR  
APPLIED TECHNOLOGY LABORATORY  
AVRADCOM  
ATTN DAVDL-ATL-TSD, TECH LIBRARY  
FT EUSTIS, VA 23604

CHIEF  
US ARMY COMMUNICATIONS SYS AGENCY  
FT MONMOUTH, NJ 07703

COMMANDER  
US ARMY COMMUNICATIONS & ELECTRONICS  
MATERIEL READINESS COMMAND  
FT MONMOUTH, NJ 07703

COMMANDER  
US ARMY COMMUNICATIONS RESEARCH &  
DEVELOPMENT COMMAND  
ATTN DRCPM-TF, OFC OF THE PM TACTICAL  
FIRE DIRECTION SYS/FIELD ARTILLERY  
TACTICAL DATA SYSTEMS  
(TACFIRE/FATDS)

# DISTRIBUTION (Cont'd)

US ARMY COMMUNICATIONS RESEARCH &  
DEVELOPMENT COMMAND (Cont'd)  
ATTN DRCPM-MSCS, OFC OF THE PM MULTI-  
SERVICE COMMUNICATIONS SYS  
ATTN DRCPM-ATC, OFC OF THE PM ARMY  
TACTICAL COMMUNICATIONS  
SYS (ATACS)  
ATTN DRDCO-PPA, PLANS, PROGRAMS &  
ANALYSIS DIR  
ATTN DRDCO-TCS, CENTER FOR TACTICAL  
COMPUTER SYS  
ATTN DRDCO-COM, CENTER FOR  
COMMUNICATIONS SYS  
ATTN DRDCO-SEI, SYS ENGINEERING  
& INTEGRATION (CENSEI)  
FT MONMOUTH, NJ 07703

COMMANDER  
US ARMY COMMUNICATIONS COMMAND  
USA COMMO AGENCY, WS  
WHITE SANDS MISSILE RANGE, NM 88002

COMMANDER  
US ARMY COMPUTER SYSTEMS COMMAND  
ATTN TECH LIB  
FT BELVOIR, VA 22060

COMMANDER  
ERADCOM TECHNICAL SUPPORT ACTIVITY  
ATTN DELSD-L, TECH LIB DIR  
FT MONMOUTH, NJ 07703

DIRECTOR  
ELECTRONICS TECHNOLOGY &  
DEVICES LABORATORY  
US ARMY ERADCOM  
ATTN DELET-DT, DIR TECHNICAL PLANS &  
PROGRAMS OFFICE  
ATTN DELET-E, DIR ELECTRONIC MATERIALS  
RESEARCH DIV  
ATTN DELET-I, DIR MICROELECTRONICS DIV  
ATTN DELET-M, MICROWAVE & SIGNAL  
PROCESSING DEVICES DIV  
FT MONMOUTH, NJ 07703

DIRECTOR  
ELECTRONIC WARFARE LABORATORY  
ATTN DELEW-SM, EW SYSTEMS MGT OFFICE  
ATTN DELEW-C, COMM INTEL/CM DIV  
ATTN DELEW-E, ELCT INTEL/CM DIV  
ATTN DELEW-V, EM VULN & ECCM DIV  
FT MONMOUTH, NJ 07703

COMMANDER  
US ARMY MATERIEL SYSTEMS ANALYSIS  
ACTIVITY  
ATTN X5 (W3JCAA)  
ABERDEEN PROVING GROUND, MD 21005

COMMANDER  
US ARMY MISSILE COMMAND  
ATTN DRCPM-CF, CHAPARRAL/FAAR  
ATTN DRCPM-HD, HELLFIRE/GLD  
ATTN DRCPM-PE, PERSHING  
ATTN DRCPM-DT, TOW DRAGON  
ATTN DRCPM-RS, GENERAL SUPPORT  
ROCKET SYS  
ATTN DRCPM-HEL, HIGH ENERGY LASER SYS  
ATTN DRCPM-ROL, ROLAND  
ATTN DRCPM-VI, VIPER  
ATTN DRCPM-HA, HAWK  
ATTN DRCPM-LC, LANCE  
ATTN DRCPM-MP, STINGER  
ATTN DRSMI-O, ADVANCED SYS CONCEPTS  
OFFICE  
ATTN DRSMI-V, COPPERHEAD  
ATTN DRSMI-T, TARGETS MANAGEMENT OFFICE  
ATTN DRSMI-U, WEAPONS SYS MGT DIR  
ATTN DRSMI-D, PLANS, ANALYSIS,  
& EVALUATION  
ATTN DRSMI-E, ENGINEERING  
ATTN DRSMI-Q, PRODUCT ASSURANCE  
ATTN DRSMI-S, MATERIEL MANAGEMENT  
ATTN DRSMI-W, MGMT INFO SYSTEMS  
REDSTONE ARSENAL, AL 35809

DIRECTOR  
US ARMY MISSILE LABORATORY  
USAMICOM  
ATTN DRSMI-RPR, REDSTONE SCIENTIFIC  
INFO CENTER  
ATTN DRSMI-RPT, TECHNICAL  
INFORMATION DIV  
ATTN DRSMI-RN, CHIEF, TECHNOLOGY  
INTEGRATION OFFICE  
ATTN DRSMI-RA, CHIEF, DARPA PROJECTS  
OFFICE  
ATTN DRSMI-RH, DIR, DIRECTED ENERGY  
DIRECTORATE  
ATTN DRSMI-RL, SPE ASST GROUND EQUIP &  
MISSILE STRUCTURES DIR  
ATTN DRSMI-RR, RESEARCH DIR  
ATTN DRSMI-RS, SYS ENGR DIR  
ATTN DRSMI-RT, TEST & EVAL DIR  
ATTN DRSMI-RD, SYS SIMULATION & DEV DIR  
ATTN DRSMI-RE, ADVANCED SENSORS DIR  
ATTN DRSMI-RK, PROPULSION DIR  
ATTN DRSMI-RG, GUIDANCE & CONTROL DIR  
REDSTONE ARSENAL, AL 35809

DIRECTOR  
NIGHT VISION & ELECTRO-OPTICS  
LABORATORY  
ATTN DELNV-D, AD FOR DEV & ENGRG  
ATTN DELNV-PA, PRODUCT ASSURANCE DIV  
ATTN DELNV-AC, ADVANCED CONCEPTS DIV  
ATTN DELNV-AC, TARGET ACQUISITION RES  
ATTN DELNV-IRT, INFRARED TECHNOLOGY DIV  
ATTN DELNV-L, LASER DIVISION



DISTRIBUTION (Cont'd)

NIGHT VISION & ELECTRO-OPTICS

LABORATORY (Cont'd)

ATTN DELNV-R, ELECTRO-OPTICS RES  
ATTN DELNV-R, ELECTRONICS MATERIALS RES  
ATTN DELNV-SE, SYSTEMS ENGINEERING DIV  
ATTN DELNV-SE, MISSILES  
ATTN DELNV-SI, SYSTEMS INTEGRATION DIV  
ATTN DELNV-SI, COMBAT VEHICLES  
ATTN DELNV-SI, OPTICS  
ATTN DELNV-SI, ELECTRONICS  
ATTN DELNV-VI, VISIONIC DIVISION  
ATTN DELNV-VI, BATTLEFIELD ENVIRONMENT  
ATTN DELNV-VI, BATTLEFIELD SYSTEMS  
PERFORMANCE  
FT BELVOIR, VA 22060

DIRECTOR

US ARMY RESEARCH & TECHNOLOGY  
LABORATORIES  
AMES RESEARCH CENTER  
MOFFETT FIELD, CA 94035

ARMY RESEARCH OFFICE (DURHAM)  
PO BOX 12211

ATTN DRXRO-EL, DIR ELECTRONICS DIV  
ATTN DRXRO-MA, DIR MATHEMATICS DIV  
ATTN DRXRO-CB, DIR CHEMICAL-BIOLOGICAL  
DIV  
ATTN DRXRO-PH, DIR PHYSICS DIV  
ATTN DRXRO-MS, METALLURGY-MATERIALS  
DIV  
ATTN DRXRO-EG, DIR ENGINEERING DIV  
RESEARCH TRIANGLE PARK, NC 27709

OFFICE OF THE DEPUTY CHIEF OF STAFF  
FOR RESEARCH, DEVELOPMENT,  
& ACQUISITION

ATTN DIR OF ARMY RES, DAMA-ARZ-A  
DR. M. E. LASSER  
ATTN DAMA-RAX, SYSTEMS REVIEW &  
ANALYSIS OFFICE  
ATTN DAMA-ZE, ADVANCED CONCEPTS TEAM  
ATTN DAMD-CSZ-A, DIR OF COMBAT  
SUPPORT SYSTEMS  
ATTN DAMA-WSZ-A, DIR OF WEAPONS SYSTEMS  
ATTN DAMA-PPZ-A, DIR OF MATERIAL PLANS  
& PROGRAMS  
ATTN DAMA-CSC, COMMAND, CONTROL,  
SURVEILLANCE SYSTEMS DIV  
ATTN DAMA-WSA, AVIATION SYSTEMS DIV  
ATTN DAMA-CSM, MUNITIONS DIV  
ATTN DAMA-WSM, MISSILES & AIR  
DEFENSE SYSTEMS DIV  
ATTN DAMA-CSS, SUPPORT SYSTEMS DIV  
ATTN DAMA-WSW, GROUND COMBAT  
SYSTEMS DIV  
WASHINGTON, DC 20317

US ARMY SATELLITE COMMUNICATIONS  
AGENCY

CORADCOM  
FT MONMOUTH, NJ 07703

DIRECTOR

US ARMY SIGNALS WARFARE LABORATORY  
VINT HILL FARMS STATION  
ATTN DELSW-RA, ANALYSIS &  
APPLICATIONS DIV  
ATTN DELSW-CE, COMMUNICATIONS/EW  
DIVISION  
ATTN DELSW-EE ELECTRONICS/EW DIVISION  
ATTN DELSW-GD, GENERAL SUPPORT SYSTEMS  
DIVISION  
ATTN DELSW-OS, OFFICE OF THE SCIENTIFIC  
ADVISOR  
ATTN DELSW-CAC, PROJECT MANAGER--  
CONTROL & ANALYSIS CENTERS OFFICE  
ATTN DELSW-M, RESOURCE MGMT & PLANS  
DIV  
ATTN DELSW-SS, SIGNAL SECURITY OFFICE  
ATTN DELSW-DT, TACTICAL DATA SYSTEMS  
DIVISION  
WARRENTON, VA 22186

COMMANDER

US ARMY TANK-AUTOMOTIVE COMMAND  
ATTN DRCPM-CVT, ARMORED COMBAT  
VEHICLE TECHNOLOGY  
ATTN DRCPM-ITV, IMPROVED TOW VEHICLE  
ATTN DRDTR-R, TANK-AUTOMOTIVE SYSTEMS  
LABORATORY  
ATTN DRDTR-Z, TANK-AUTOMOTIVE CONCEPTS  
LABORATORY  
ATTN DRDTR-T, DIR FOR ENGINEERING  
SUPPORT  
ATTN DRDTR-J, DIR FOR PRODUCT ASSURANCE  
28251 VAN DYKE AVENUE  
WARREN, MI 48090

COMMANDER

US ARMY TEST & EVALUATION  
COMMAND  
ABERDEEN PROVING GROUND, MD 21005

COMMANDER

WHITE SANDS MISSILE RANGE  
DEPT OF THE ARMY  
ATTN STEWS-CE, COMMUNICATIONS/  
ELEC OFFICE  
WHITE SANDS MISSILE RANGE, NM 88002

COMMANDER

US ARMY ELECTRONICS PROVING GROUND  
FT HUACHUCA, AZ 85613

DISTRIBUTION (Cont'd)

ASSISTANT SECRETARY OF THE NAVY  
RESEARCH, ENGINEERING, & SYSTEMS  
DEPT OF THE NAVY  
WASHINGTON, DC 20350

COMMANDER  
NAVAL AIR DEVELOPMENT CENTER  
ATTN TECHNICAL LIBRARY  
WARMINSTER, PA 18974

CHIEF OF NAVAL OPERATIONS  
DEPT OF THE NAVY  
ATTN DIR, COM & CONTR &  
COMMUNICATIONS PROGRAMS  
WASHINGTON, DC 20350

SUPERINTENDENT  
NAVAL POSTGRADUATE SCHOOL  
ATTN LIBRARY, CODE 2124  
MONTEREY, CA 93940

DIRECTOR  
NAVAL RESEARCH LABORATORY  
ATTN 2600, TECHNICAL INFO DIV  
ATTN 2750, OPTICAL SCIENCES DIV  
ATTN 5500, OPTICAL SCI DIV  
ATTN 6000, MATL & RADIATION  
SCI & TE  
WASHINGTON, DC 20375

COMMANDER  
DAVID W. TAYLOR NAVAL SHIP R&D CENTER  
BETHESDA, MD 20084

COMMANDER  
NAVAL SURFACE WEAPONS CENTER  
ATTN DX-21, LIB DIV  
DAHLGREN, VA 22448

COMMANDER  
NAVAL SURFACE WEAPONS CENTER  
ATTN F30, NUCLEAR EFFECTS DIV  
ATTN R-40, RADIATION DIV  
ATTN R-42, ELECTRO-OPTICS BR  
ATTN X22, TECHNICAL LIB  
WHITE OAK, MD 20910

COMMANDER  
NAVAL TELECOMMUNICATIONS COMMAND HQ  
ATTN TECHNICAL LIBRARY  
4401 MASS AVE NW  
WASHINGTON, DC 20390

COMMANDER  
NAVAL WEAPONS CENTER  
ATTN 38, RESEARCH DEPT  
ATTN 381, PHYSICS DIV  
CHINA LAKE, CA 93555

COMMANDER OFFICER  
NAVAL WEAPONS EVALUATION FACILITY  
KIRTLAND AIR FORCE BASE  
ALBUQUERQUE, NM 87117

DEPUTY CHIEF OF STAFF  
RESEARCH & DEVELOPMENT  
HEADQUARTERS, US AIR FORCE  
ATTN AFRDQSM  
WASHINGTON, DC 20330

AIR FORCE AVIONICS LABORATORY  
ATTN KJA (TEO), ELECTRO-OPTICS  
TECHNOLOGY BR  
WRIGHT-PATTERSON AFB, OH 45433

COMMANDER  
AF ELECTRONIC SYSTEMS DIVISION  
ATTN WO, DEP FOR CONTROL  
& COMMUNICATIONS SYS  
LG HANSCOM AFB, MA 01730

RELIABILITY ANALYSIS CENTER  
RADC (RBRAC)  
GRIFFISS AFB, NY 13441

COMMANDER  
HQ ROME AIR DEVELOPMENT CENTER (AFSC)  
ATTN LE, DEPUTY FOR ELECTRONIC TECH  
ATTN LMT, TELECOMMUNICATIONS BR  
GRIFFISS AFB, NY 13441

DIRECTOR  
AF OFFICE OF SCIENTIFIC RESEARCH  
BOLLING AFB  
ATTN NE, DIR OF ELECTRONIC &  
SOLID STATE SCI  
WASHINGTON, DC 20332

COMMANDER  
HQ AIR FORCE SYSTEMS COMMAND  
ANDREWS AFB  
ATTN TECHNICAL LIBRARY  
WASHINGTON, DC 20334

AF WEAPONS LABORATORY, AFSC  
ATTN EL, ELECTRONICS DIV  
ATTN LR, LASER DEV DIV  
KIRTLAND AFB, NM 87117

DIRECTOR  
NASA  
ATTN TECHNICAL LIBRARY  
JOHN F. KENNEDY SPACE  
CENTER, FL 32899

DIRECTOR  
NASA  
LANGLEY RESEARCH CENTER  
ATTN TECHNICAL LIBRARY  
HAMPTON, VA 23665

DISTRIBUTION (Cont'd)

DIRECTOR  
NASA  
LEWIS RESEARCH CENTER  
ATTN TECHNICAL LIBRARY  
CLEVELAND, OH 44135

JET PROPULSION LABORATORY  
CALIFORNIA INSTITUTE OF TECHNOLOGY  
4800 OAK GROVE DRIVE  
ATTN TECHNICAL LIBRARY  
PASADENA, CA 91103

LAWRENCE LIVERMORE NATIONAL LABORATORY  
PO BOX 808  
LIVERMORE, CA 94550

SANDIA LABORATORIES  
LIVERMORE LABORATORY  
PO BOX 969  
LIVERMORE, CA 94550

SANDIA NATIONAL LABORATORIES  
PO BOX 5800  
ALBUQUERQUE, NM 87185

US ARMY ELECTRONICS RESEARCH  
& DEVELOPMENT COMMAND  
ATTN TECHNICAL DIRECTOR, DRDEL-CT

HARRY DIAMOND LABORATORIES  
ATTN CO/TD/TSO/DIVISION DIRECTORS  
ATTN RECORD COPY, 81200  
ATTN HDL LIBRARY, 81100 (3 COPIES)  
ATTN HDL LIBRARY, 81100 (WOODBIDGE)  
ATTN TECHNICAL REPORTS BRANCH, 81300  
ATTN LEGAL OFFICE, 97000  
ATTN CHAIRMAN, EDITORIAL COMMITTEE  
ATTN MORRISON, R. E., 13500 (GIDEP)  
ATTN CHIEF, 21000  
ATTN CHIEF, 21100  
ATTN CHIEF, 21200  
ATTN CHIEF, 21300  
ATTN CHIEF, 21400  
ATTN CHIEF, 21500  
ATTN CHIEF, 22000  
ATTN CHIEF, 22100  
ATTN CHIEF, 22300  
ATTN CHIEF, 22800  
ATTN CHIEF, 22900  
ATTN CHIEF, 20240  
ATTN B. ROD, 21100  
ATTN R. GARVER, 21100  
ATTN H. BRISKER, 21100  
ATTN C. FAZI, 21100  
ATTN J. VANDERWALL, 22800  
ATTN R. GILBERT, 22800 (30 COPIES)  
ATTN J. BLACKBURN, 22800 (30 COPIES)

5-83

DTIC

**FILMED**

**5-83**

**DTIC**